# ESTIMATE

**Qunnect, Inc**
141 Flushing Ave (Bldg 77) Ste 1110
New York, NY 11205

audrey@quconn.com
+1 (713) 398-9175
www.qunnect.inc

## Santa Fe Community College

**Bill to**
Brian Rashap/ Monique Anair
Central New Mexico Community College
525 Buena Vista Dr SE
Albuquerque, NM 87106

**Estimate details**
Estimate no.: 2026-0731-1
Estimate date: 07/28/2026
Expiration date: 12/31/2026

Lead Time: 6 months
Payment method: ACH/Wire

| # | Product or service | Description | Qty | Amount |
|---|---|---|---|---|
| 1. | **1 Node Carina Scalable Networking System** | Full stack networking system for establishing a single node of an entanglement distribution network. | 1 | $1,000,000.00 |
| 2. | **Qu-SRC with pump lasers & atomic reference** | Bichromatic photon pairs at 1324nm and 795nm<br>High fidelity \|HH>+\|VV> Bell states<br>10M pairs/s Pair Generation Rate<br>Ultra narrow photonic linewidth (sub-GHz)<br>Includes:<br>- Qu-LSR Dual pump lasers (1367nm/780nm)<br>- Qu-LCK Atomic reference for telecom and NIR lasers | 1 | $0.00 |
| 3. | **Qu-APC** | Qu-APC Compensator:<br>Compensation & fast measurement station.<br>- Arbitrary polarization stabilization through time-multiplexing<br>- Max average fidelity of 98%<br>- Input-output loss of <2dB.<br>- Fast 1-10 kHz polarimeter<br><br>Qu-APC Injector:<br>Automated telecom injector for polarization reference.<br>- Internal SFP laser at O band<br>- Input ports for external laser<br>- Input/output ports + internal optical switch for time multiplexing | 1 | $0.00 |
| 4. | **Qu-Val** | Automated entanglement validation module:<br>- Real-time monitoring of the quantum link | 1 | $0.00 |

| | | | | |
|---|---|---|---|---|
| | | - Reporting the throughput rate and QBER<br>- Providing statistics on the entanglement source<br>- Includes <100ps time synchronization and time tagging electronics to auto-sync with neighboring Qu-racks.<br>- Includes the Qu-Val software for remote access and monitoring the network performance. | | |
| 5. | **Qu-Measure Telecom (SNSPD)** | Superconducting Nanowire Single Photon Detector (SNSPD)<br>- 8 channel<br>- High Count Rate + Low Jitter | 1 | $0.00 |
| 6. | **Qu-SYNC** | Timing Electronics:<br>- 4 channel TDC with ultra-low jitter and high bandwidth<br>- <100ps time synchronization to to sync with neighboring Qu-racks | 1 | $0.00 |
| 7. | **Wavelength multiplexing OADM DWDM** | C-band DWDM 48Ch 100G spacing with monitor & low-loss 1310nm port (LC/UPC) | 1 | $0.00 |
| 8. | **Rack-Mounted Router** | - 3.5+ Gbps routing with IDS/IPS<br>-10G SFP+*, (8) GbE RJ45 LAN ports<br>-10G SFP+*, (1) GbE RJ45 WAN ports<br>-1.3" touchscreen<br>-3.5" NVR HDD bay | 1 | $0.00 |
| 9. | **Server** | Intel Xeon processor, 4-Core, 8 Threads 4x 1GbE, 2x 10GBase-T, 2x 10G SFP+ and 1 dedicated LAN for IPMI 2.0 | 1 | $0.00 |
| 10. | **QU-Orchestrator** | Main Control Software<br>- Remote monitoring and control of QU-Rack components<br>- Orchestrates the operation of all devices for optimal network uptime and performance | 1 | $0.00 |
| 11. | **Qu-Rack** | 37U rack with integrated UPS, PID and cooling system suitable for housing quantum instruments. | 1 | $0.00 |
| 12. | **Discount** | Academic Discount on above items | 1 | –$50,000.00 |
| 13. | **Discount** | Repeat Customer Discount | 1 | –$10,000.00 |
| 14. | **Domestic Installation (daily rate)** | On site installation of product(s) by Qunnect Staff | 3 | $3,000.00 |
| 15. | **Training (daily rate)** | On site Training of users by Qunnect Staff | 3 | $3,000.00 |
| 16. | **Shipping** | Dedicated Truck Freight | 1 | $7,000.00 |

## Ways to pay

BANK

Thank you for your business. We accept ACH and wire transfers.

| | |
|---|---|
| **Total** | **$953,000.00** |
| Deposit due | $476,500.00 |
| Expiry date | 12/31/2026 |

## Note to customer

50% of the cost will be invoiced upon receipt of the purchase order.
The remainder will be billed Net 30 upon receipt

---

**Accepted date** **Accepted by**